

SURVEY &
REMONUMENTATION

LIBER 1810 PAGE 30

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MUSKEGON COMMISSION
(County)

Located In: Corner Code #

1. Public Land Survey	T	9N	R	15W	E-2
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

A1537

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD
1994 DEC 27 AM 11:41
Dorinda Carter
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4	3	2	1					
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEPHEN V. VALLIER, in a field survey on OCTOBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 CORNER SET BY GLO
N 27° E 5 LINKS 100" MAPLE
N 34° W 5 LINKS 6" BEECH

1950'S M.C.R.C. IRON PIPE
NE 28.87' 14" B. OAK
SE 72.39' P. POLE
SW 105.40' 8" B. OAK
NW 67.2 8" W. OAK

1981 C.F. LEWANDOWSKI, LBR. 1211, PG. 143
FOUND RAILROAD SPIKE
N 43° E 37.95' P. POLE
S 20° E 72.58' P. POLE
N 40° W 67.75' 16" OAK
NE 88.05' 4" OAK
SE 93.75' 12" OAK

1991 R. VANRIPER LBR. 1573, PG. 374
FOUND 1/2" IRON ROD IN MON. BOX
N 71° E 45.11' U. POLE
S 39° E 51.03' "X" IN CONC. CURB
S 60° W 59.56' G. POLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: N 43° W 55.82' T. POLE
FOUND RAILROAD SPIKE - ACCEPTED POSITION OF CORNERS DUE TO HISTORICAL USAGE AND DOCUMENTATION

(Filed in wrong town & range (T9N, R16W))


Sept. 6 1994

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 30" CAST IRON MON. WITH COUNTY SURVEY CAP-REPLACED RAILROAD SPIKE
N 48° E 37.92' NAIL N. SIDE P. POLE
S 20° E 72.53' NAIL N. SIDE P. POLE
N 35° W 67.68" NAIL S. SIDE 18" OAK
S 33° W 99.48' NAIL E. SIDE 18" OAK
S 44° W 103.37' NAIL S. SIDE 22" OAK
N 45° W 88.87' NAIL W. SIDE 26" OAK
N 49° W 75.58' NAIL N. SIDE 36" OAK

Signed by _____



Date Dec 27, 1994

Surveyor's Michigan License No. 28428 No. 28428