

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

MUSKEGON
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 9N R 15W | E-11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

A1554

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECORDS & RECORDS
REGISTER OF DEEDS
1994 DEC 27 AM 11:42

Register of Deeds Stamp & File Number

I, **STEPHEN V. VALLIER**, in a field survey on DECEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO SET SECTION CORNER	1990 R. VANRIPER LBR. 1542, PG. 362
N 42° E 11 LINKS 12" HEMLOCK	STAN SHACKELFORD FOUND "T" IRON OVER
N 53° W 10 LINKS 12" HEMLOCK	1" X 2" PIPE

1950'S M.C.R.C.
N 70.8' 4" CHERRY
SE 112.53 10" W.O.
SW 51.79' 3RD FENCE POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" CAST IRON MONUMENT WITH COUNTY SURVEY CAP IN ACCEPTED POSITION OF CORNER DUE TO HISTORICAL USAGE AND CONSISTENT DOCUMENTATION

N 54° E 51.78'	NAIL S. SIDE 10" ASH
N 9° E 55.81'	NAIL E. SIDE P. POLE
S 24° E 34.60'	NAIL E. SIDE 4-6" TWIN ELM
S 55° E 66.72'	NAIL N. SIDE 8" ELM
S 33° E 74.76'	NAIL W. SIDE 4-6" TWIN ELM

Aug 2, 1994

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 4" CAST IRON MONUMENT WITH COUNTY SURVEY CAP

N 54° E 51.78'	NAIL S. SIDE 10" ASH
N 9° E 55.81'	NAIL E. SIDE P. POLE
S 24° E 34.60'	NAIL E. SIDE 4-6" TWIN ELM
S 55° E 66.72'	NAIL N. SIDE 8" ELM
S 33° E 74.76'	NAIL W. SDIE 4-6" TWIN ELM

Signed by

[Signature]

Date

Dec 27, 1994

Surveyor's Michigan License No.

28428 Surveyor No. 28428

