

1993

LIBER 1744 PAGE 556

STATE OF MICHIGAN
COUNTY OF MUSKEGON
REGISTERED FILE RECORD

1993 DEC 29 PM 4:03

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MUSKEGON

(County)

Located In:

Corner Code //

1. Public Land Survey

T 9N R 15W

F-2

T R

T R

T R

T R

2. Property Controlling
in Section

S

S

T

T

R

R

3. Miscellaneous
Property in Sec.

S

S

T

T

R

R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Carrie Carter
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5				3		2					
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEPHEN V. VALLIER in a field survey on NOVEMBER 11, 1993 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET BY G.L.O. SURVEY

1/2" IRON ROD SET BY L.F. LEWANDOWSKI, OCT. 1980
RECORDED LIBER 1211, PAGE 143

1 1/4" IRON PIPE M.C.R.C. 1955

LOCATED 54.47' EAST AND 4.36' NORTH OF 1 1/4" PIPE

NW NE SOUTH
78.88' 29.85' 23.45'
10" OAK 6" OAK 18" OAK

NORTH N20°W N48°E S47°E S37°W
33.00' 29.90' 33.00' 58.30' 53.85'
1/2" IRON 14" TWIN 9" OAK 16" OAK 10" OAK
ROD OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD RECORDED IN LIBER 1211, PAGE 143

1 1/4" IRON PIPE 54.47' WEST AND 4.36' SOUTH OF FOUND 1/2" IRON ROD

S 40°W S 45°E
53.79' 58.23'
10" TWIN OAK 16" OAK

HISTORICAL USAGE, DOCUMENTATION & EVIDENCE OF DOUBLE CORNERS REVIEWED BY MUSKEGON COUNTY PEER GROUP. AFTER EXAMINING THE EVIDENCE, IT WAS THE DECISION TO ACCEPT CENTER OF SECTION SET BY C.F. LEWANDOWSKI (INTERSECTION OF 1/4 LINES). CORNER LOCATION RATIFIED NOV. 16, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP IN PLACE OF 1/2" IRON ROD RECORDED IN LIBER 1211, PAGE 143.

1 1/4" PIPE 54.47' WEST AND 4.36' SOUTH

NORTH	S 20°E	N 32°E	S 40°W	N47°W	S 45°E
33.35'	52.13'	37.60'	53.79'	63.73'	58.23'
FACE 4'	8" OAK	6" OAK	10" TWIN OAK	6" OAK	16" OAK
RAILROAD TIE	(FOUND NAIL SE'LY SIDE)	(FOUND NAIL E'LY SEDE)	(FOUND NAIL NW'LY SIDE)	(FOUND NAIL NORTH SIDE)	(FOUND NAIL SW'LY SIDE)

Signed by STEPHEN V. VALLIER

Date

Dec 28, 1993

Surveyor's Michigan License No. 28428

