

1993

1993 DEC 29 PM 4:03

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MUSKEGON
(County)

Located In: Corner Code #

1. Public Land Survey	T	9N	R	15W	F-3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Carrie Carter
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

STEPHEN V. VALLIER in a field survey on NOVEMBER 22, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. CORNER SET BY J. MULLETT MAY 4, 1837
8" PINE AT CORNER

IRON-MUSKEGON COUNTY ROAD COMMISSION 1955
NW SW SE
63.56' 59.68' 54.29'
P. POLE 30" OAK 8" TRI. OAK

1 1/4" IRON PIPE IN MON. BOX M.C.R.C. - JULY 1976, REC. IN LIBER 1087, PAGE 691
NW SSW SE ESE
64.98' 45.74' 53.45' 72.49'
P. POLE 5" PINE TRI OAK 12" OAK
FOUND 1 1/4" PIPE IN MON. BOX-D. SANDEL DEC. 1987/REC. LBR. 1421, PAGE 737
NW SSW ESE
64.88' 45.74' 72.49'
P. POLE 5" PINE 12" OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" X 24" IRON PIPE IN MON. BOX
N 30° W S 45° E
64.95' 54.22'
P. POLE 16" TWIN OAK

HISTORICAL USAGE, DOCUMENTATION & EVIDENCE OF CORNER LOCATION REVIEWED AND RATIFIED BY MUSKEGON COUNTY PEER GROUP JUNE 15, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 2 3/4" X 20" CAST IRON MONUMENT WITH COUNTY SURVEY CAP IN MONUMENT BOX (REPLACED IRON PIPE REC. LBR. 1087, PAGE 691)
N 30°W S 48°W S45°E N31°E N74°W S60°E N
64.95' 64.99' 54.22' 93.08' 113.31' 87.53' 33.00'
P. POLE 10" PINE 16" TW. OAK 10" OAK 10" WH. PINE 8" TW. OAK FD. CAPPED
(FD. NAIL (FD. NAIL (FD. NAIL (FD. NAIL (SET NAIL (SET NAIL IRON ROD
W'LY SIDE) NW'LY SIDE) NE'LY SIDE) SE'LY SIDE) (S'LY SIDE) SW'LY SIDE)

Signed by STEPHEN V. VALLIER Date 11/22/93
Surveyor's Michigan License No. 28428

