

1993 DEC 29 PM 4:03

*Carlin Carter*  
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MUSKEGON  
(County)

Located In: Corner Code //

- 1. Public Land Survey T 9N R 15W F-4
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

**SURVEY &  
REMONUMENTATION**

**NOV 28 2000**

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEPHEN V. VALLIER in a field survey on NOVEMBER 23, 19 93  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
CORNER NOT SET BY G.L.O. SURVEY

FOUND 1" IRON WESTSHORE ENG. & SURVEY-OCT.  
N SSE N SE  
86.28" 96.24' 142.6' 278.2'  
CENTERLINE 10" OAK 5' PIPE NW COR.  
RAILROAD CONSUMERS  
POWER TOWER

"T" IRON SET AT INTERSECTION OF 1/4 LINES  
BY WILLIAMS & WORKS 1960

N SSE  
89.19' 96.24'  
CENTER- 10" OAK  
LINE RAILROAD

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1" X 18" IRON PIPE

N E S 15° E  
86' ± 277.6' ± 96.20'  
CENTERLINE OF NW LEG OF 22" OAK  
ABANDONED TRANSMISSION  
RAILROAD TOWER

HISTORICAL USAGE, DOCUMENTATION & EVIDENCE OF CORNER LOCATION REVIEWED & RATIFIED BY MUSKEGON  
COUNTY PEER GROUP OCTOBER 5, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP (REPLACED FOUND 1" X 18" PIPE)

S88°W	S39°W	S15°E	S45°E	N11°W	N68°E
156.14'	113.49'	96.20'	182.71'	189.06'	225.23'
12" OAK	10" OAK	22" OAK	20" OAK	16" OAK	10" TW. OAK
(SET NAIL	(FD. NAIL	(FD. NAIL	(SET NAIL	(SET NAIL	(SET NAIL
S'LY SIDE)	W'LY SIDE)	NE'LY SIDE)	NE'LY SIDE)	W'LY SIDE)	S'LY SIDE)

Signed by STEPHEN V. VALLIER

Date

*Dec 28 1993*

Surveyor's Michigan License No. 28428

