

1993

LIBR 1744 PAGE 566

1993 DEC 29 PM 4:04

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Carrie Carter*  
REGISTER OF DEEDS

For corners in

Muskegon <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>9N</u> R <u>15W</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*11/13/97*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephen V. Vallier, in a field survey on November 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
G.L.O. corner set by J. Mullett, May 3, 1837

N 65 Deg. WEST	S 14 Deg. WEST	5/8 Iron	Nov. 1974
14 links	5 Links	Rec. Lbr. 1050 P. 16	
12" Hemlock	6" Hemlock	NNE NNW	S
		48.70'	59.24'
		Poplar	8" Poplar
			Fence Post
		NW	SSW
2" Iron stake M.C.R.C. 1955		38.3'	191.0'
		2" Poplar Tree	Fence Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" x 18" rod placed over 1" x 3' pipe  
N 13 Deg. E  
48.6'  
12" Aspen Stump

HISTORICAL USAGE, DOCUMENTATION & EVIDENCE OF CORNER LOCATION REVIEWED AND RATIFIED BY MUSKEGON COUNTY PEER GROUP OCTOBER 5, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" x 30" cast iron monument with county survey cap  
(Replaced 5/8" x 18" rod Rec. in Lbr. 1050 P. 16)

N 73 Deg. E	N 25 Deg. E	N 39 Deg. W	S 41 Deg. W	S	S 51 Deg. E	N 13 Deg. E
118.54'	87.17'	46.25'	35.92'	32.90'	57.18'	48.6 +/-
10" Aspen	14" W. Pine	6" Aspen	6" Aspen	Found	4" Aspen	12" Aspen stump
(Set nail S'ly side)	(Set nail W'ly side)	(Found nail SW'ly side)	(Set nail NW'ly side)	iron rod	(Set nail NE'ly side)	Found nail

Signed by Stephen V. Vallier

Date Dec 25, 1993

Surveyor's Michigan License No. 28428

