

APR 28 1995

LIBER 1810 PAGE 39

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MUSKEGON

(County)

Located In:

Corner Code #

1. Public Land Survey	T	9N	R	15W	F-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

A 1346

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD
1994 DEC 27 AM 11:42
C. J. Carter
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, STEPHEN V. VALLIER, in a field survey on NOVEMBER, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET BY GLO	1980 M.C.R.C., LBR. 1203, PG. 545
1950'S M.C.R.C.	FOUND RAILROAD SPIKE, RESET 1/2" REROD IN
IRON PIPE	MON. BOX
NE 42.6' P. POLE	SW 86.22' 24" MAPLE
SE 52.85' 12" MAPLE	NW 49.60' 10" PINE
SSW 57.20' TWIN 40" CHERRY	NE 39.17' T. POLE
	SW 48.18' T. POLE
	SE 52.56' 24" MAPLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" X 18" ROD ON MON. BOX. CORNER RESET IN 1966 BY F.F. SMITH TO M.C.R.C. TIES. CORNER APPEARS TO BE SET BY SINGLE PROPORTIONATE MEASURE ALONG E-W 1/4 LINE. ORIGIN UNDETERMINED HOWEVER DUE TO OCCUPATION AND HISTORICAL USAGE

SW 86.13' 26" MAPLE STUMP
SE 52.86' 30" MAPLE

Aug 2, 1994
POSITION OF SAID
CORNER POINTS
REESTABLISHED
BY LAND SURVEYOR
STEPHEN V. VALLIER
MUSKEGON COUNTY
MICHIGAN BOARD OF LAND SURVEYORS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 2 3/4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP (REPLACED 1/2" IRON ROD) IN MON. BOX

N 58° W	68.16'	NAIL S. SIDE 16" W. PINE
N 63° W	116.80'	NAIL S. SIDE 14" R. PINE
N 20° W	43.61'	NAIL W. SIDE 10" R. PINE
N 22° E	102.52'	NAIL S. SIDE 36" TRIPLE MAPLE
S 49° E	52.86'	NAIL IN N. SIDE 30" MAPLE
S 56° W	86.13'	NAIL IN N. SIDE 36" MAPLE STUMP

Signed by

[Signature]

Date

Dec 27, 1994

Surveyor's Michigan License No.

28428

