

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION
MUSKEGON
(County)

Located In: Corner Code #

- 1. Public Land Survey T 9N R 15W E-9
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

A 1547

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED
1991 DEC 27 AM 11:42
Doris Carter
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, STEPHEN V. VALLIER in a field survey on DECEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 GLO SET 1/4 CORNER
N 30° E 7 LINKS 6" HEMLOCK
S 37° W 13 LINKS 6" HEMLOCK
1970'S M.C.R.C TIE BACK (C.P. ENGLERT)
1" IRON PIPE
NNE 6.3' 4" ASPEN
WNW 40.2' 6" ASPEN
SSW 9.6' 4" ASPEN
- 1994 U.S. FORESTRY SERVICE
FOUND 1" IRON PIPE 40' WEST OF N-S DOWNED
BARB WIRE FENCE
N 41° E 6.3' 8" ASPEN
N 71° W 40.2' 10" ASPEN
S 18° W 9.6' 7" ASPEN
B. OAK 30.9' 7" OAK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1 1/2" IRON PIPE (48" LENGTH) N 2' TO E-W FENCE AND WEST 38' FENCE TO SOUTH. ACCEPTED POSITION OF FOUND CORNER. EVIDENCE INDICATES CORNER WAS SET BY SINGLE PROPORTIONATE MEASURE. ORIGIN UNKNOWN HOWEVER HISTORICAL USE IS CONSISTENT WITH KNOWN CORNER.

Aug 2, 1994 SW
POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1980

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP-REPLACED 1" IRON
N 82° W 24.82" NAIL S. SIDE 8" MAPLE
N 58° W 31.05' NAIL W. SIDE 12" TWIN MAPLE
S 75° W 46.07' NAIL S. SIDE 16" POPLAR
S 45° E 34.12' NAIL S. SIDE 8" TWIN MAPLE
N 69° W 12.05' NAIL S. SIDE 10" MAPLE
S 7° W 35.71' NAIL S. SIDE 8" MAPLE

Signed by [Signature] Date Dec 27, 1994
Surveyor's Michigan License No. 28428
