

1993 DEC 29 PM 4: 03

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Carrie Carter
REGISTER OF DEEDS

For corners in
MUSKEGON
(County)

Located In: Corner Code //

- 1. Public Land Survey T 9N R 15W G-1
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

SURVEY &
REMONUMENTATION

NOV 28 2000

Register of Deeds Stamp & File Number

SECTION

- 4. Lot No: _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **STEPHEN V. VALLIER**, in a field survey on **NOVEMBER 19**, 19 **93**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. CORNER SET BY J. MULLETT, MAY 2, 1837

.88 LINKS EAST OF POST

S 44° W S 78° W
21 LINKS 49 LINKS
6" BEECH W. OAK

SET 1/2" IRON ROD C.F. LEWANDOWSKI, FEB-19, RECORDED IN LBR. 1211, PG. 141
WEST N76°E S 30°E S 30°W N6°E
58.08' 36.70' 41.25' 42.40' 39.4'
1/2" 10" 10" 13" 10"
ROD OAK OAK OAK OAK
(SE CORNER
SEC. 33
T10N, R15W)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD

W N76°E S30°E S34°W N6°E
58.05' 36.73' 41.20' 42.31' 39.33'
FOUND 1/2" 10" OAK 10" OAK 12" OAK 12" OAK
IRON ROD

C.F. LEWANDOWSKI SET AS LOST CORNER BY SINGLE PROPORTIONATE METHOD. AGREES WITH G.L.O. CLOSING DISTANCE. HISTORICAL USAGE, DOCUMENTATION & EVIDENCE OF CORNER LOCATION REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP NOV. 2, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP. (REPLACED CORNER RECORDED IN LBR. 1211, PAGE 141)

WEST N76°E S 30°E S 34°W N6°E WEST
58.05' 36.73' 41.20' 42.31' 39.33' 14.97'
FD. 1/2" IRON
ROD 10' OAK 10" OAK 12" OAK 12" OAK 10" TW. OAK
(SE COR. SEC. (FOUND NAIL (FOUND NAIL (FOUND NAIL (FOUND NAIL (SET NAIL
33, T10N, S'LY SIDE) SW'LY SIDE) SE'LY SIDE) E. SIDE) (S. SIDE)
R15W)

Signed by **STEPHEN V. VALLIER**

Date

Surveyor's Michigan License No. 28428

