

1993 DEC 29 PM 4:02

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MUSKEGON

*Carrie Carter*  
REGISTER OF DEEDS

Located In: \_\_\_\_\_ Corner Code: #/

(County)

1. Public Land Survey T 9N R 15W G-7  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S T R  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S T R  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, STEPHEN V. VALLIER, in a field survey on NOVEMBER 11, 19 93  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO CORNER SET BY J. MULLETT, 5-1-1837

N 85°E N 1°E  
7 LINKS 6 LINKS  
12" HEMLOCK 14" B. ASH

FD. 3" PIPE-J. CAMPBELL, JAN. 1980  
RECORDED IN LBR. 1188, PG. 209

S 30°E S 10°W N 45°E  
41.75' 31.50' 45.10'  
12" W. PINE 8" MAPLE 12" SCOTCH  
PINE

REINF. ROD-M.C.R.C.-1955

ENE SE NW  
45.3' 59.25' 47.45'  
6" POP. 5" POP. T. POLE

FD. 3/4" IRON PIPE  
N 60°E S 74°E N 61°W  
47.15' 45.02' 42.77' 57.80'  
P. POLE POP. POP. MAPLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" X 18" PIPE OVER AND 1 1/4" X 18" IRON PIPE

N 60° E  
45.04'  
12" ASPEN

HISTORICAL USAGE, DOCUMENTATION AND EVIDENCE OF CORNER LOCATION REVIEWED AND RATIFIED BY  
MUSKEGON COUNTY PEER GROUP SEPT. 9, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP (REPLACED 1" X 18" PIPE)

N 60°W	N 30°W	N 60°E	S 62°W	S 65°E	S 14°E
57.80'	47.13'	45.04'	52.02'	42.73'	103.45'
16" MAPLE	P. POLE	12" ASPEN	6" W. CHERRY	12" ASPEN	12" ASPEN
(FD. NAIL N'LY SIDE)	(FD. NAIL SW'LY SIDE)	(FD. NAIL NW'LY SIDE)	(SET NAIL N'LY SIDE)	(FD. NAIL N'LY SIDE)	(SET NAIL NE'LY SIDE)

Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 28428

