

1993

LIB: 1744 FILE 562

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1993 DEC 29 PM 4:03

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Carrie Carter
REGISTER OF DEEDS

For corners in
MUSKEGON
(County)

Located In: Corner Code: //

- 1. Public Land Survey T 9N R 15W H-1
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEPHEN V. VALLIER, in a field survey on DECEMBER 14, 19 93
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
CORNER NOT SET BY GLO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
NO MONUMENT, EVIDENCE OR DOCUMENTATION OF CORNER BEING PERPETUATED.
SET 4" X 30" CAST IRON MONUMENT BY SINGLE PROPORTIONATE MEASURE. THIS IS CONSISTENT
WITH PROCEDURES USED BY C.F. LEWONDOWSKI TO EST. F-1 & G-1.

METHOD OF PROCEDURE & EVIDENCE REVIEWED AND RATIFIED BY MUSKEGON COUNTY PEER GROUP
ON DECEMBER 14, 1993


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP
WEST SOUTH WEST S 70°E N 11°E N 42°W S 70°W S 12°E S 28°E
68± 4' 71.07' 11.72' 27.18' 61.43' 46.50' 92.31' 23.33'
FENCE E-W FD. 5/8" 12" OAK 12" OAK 12" OAK 10" OAK 28" OAK 8" OAK
TO FENCE IRON ROD (SET N'LY (SET E'LY (SET NAIL (SET NAIL (SET NAIL (SET NAIL SW'LY SIDE)
NORTH (S 1/2 COR. SIDE) SIDE) SE'LY SIDE) SE'LY SIDE) W'LY SIDE)
SEC. 33
T10N, R15W)

Signed by

Stephen V. Vallier
STEPHEN V. VALLIER

Surveyor's Michigan License No.

28428



Date

Dec. 28, 1993