

1993

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED

1993 DEC 29 PM 4:0

*Carrie Carter*  
REGISTER OF DEEDS

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MUSKEGON

(County)

Located In:

Corner Code: #

- 1. Public Land Survey T 9N R 15W H-3  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, STEPHEN V. VALLIER, in a field survey on NOVEMBER 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO CORNER SET BY J. MULLETT, 5-2-1837

N 36°E

3 LINKS

10" HEMLOCK

FD. 1 1/2" IRON PIPE IN MON. BOX-WESTSHORE

ENG. & SURVEY-JUNE 1987

NE

SE

S

65.78'

77.30'

27.03'

P. POLE

NW COR HSE.

18" MAPLE

1 1/2" IRON PIPE IN MON. BOX (FOUND R/R SPIKE REC.

IN LBR. 1087, PG. 671) -M.C.R.C. JULY 1976

NE S SE SSW NNW

65.78' 27.09' 77.30' 80.52' 81.65'

P. POLE 20" MAP. NW CNR. HSE. 16" MAP. CHERRY CLUMP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/2" X 24" IRON PIPE IN MONUMENT BOX

N 40°E S 2°E S 41° E N 17°W

65.72' 27.09' 77.30' 81.51'

P. POLE 16" MAP. NW CNR. HSE. W. CHERRY CLUMP

HISTORICAL USAGE, DOCUMENTATION AND EVIDENCE OF CORNER LOCATION REVIEWED AND RATIFIED BY MUSKEGON COUNTY PEER GROUP, JUNE 15, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 2 3/4" X 20" CAST IRON MONUMENT WITH COUNTY SURVEY CAP IN MONUMENT BOX (REPLACED 1 1/2" X 24" IRON PIPE RECORDED IN LBR. 1087, PAGE 671)

N 40° E	S 2° E	S 41° E	N 17° W	N 66° W	S 73° W
65.72'	27.09'	77.30'	81.51'	96.65'	102.93'
P. POLE	16" MAPLE	NW COR HSE	W. CHERRY	6" W. PINE	18" TW. OAK
(FD. NAIL	(FD. NAIL	CONC. BLK	(FD. NAIL	(SET NAIL	(SET NAIL
NW'LY SIDE)	W'LY SIDE)	FOUNDATION	SE'LY SIDE)	S'LY SIDE)	N'LY SIDE)

Signed by Stephen V. Vallier  
Surveyor's Michigan License No. 28428

