

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Carlin Carter
REGISTER OF DEEDS

For corners in
MUSKEGON
(County)

Located In: Corner Code //

- 1. Public Land Survey T 9N R 15W H-6
T R
T R
T R
- 2. Property Controlling S T R
in Section S I R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. Recorded Plat
- 5. Private Claims

Register of Deeds Stamp & File Number

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, **STEPHEN V. VALLIER** in a field survey on **SEPTEMBER 20**, 19**93**
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
CORNER NOT SET BY GLO

FOUND 1" PIPE-J. CAMPBELL-JAN. 1980
(RECORDED LBR. 1188, PG. 210)
N 70°E S 70°E N 15°W
40.51' 45.35' 47.55'
20" MAPLE 12" TW. MAP. 30" BEECH

IRON-M.C.R.C.-1955
EAST NORTH WNW
26.13' 52.20' 25.05'
10" POP. 8" POP. 24" B. OAK
3/4" IRON PIPE-D. SCHIELE-JAN. 1992
REC. LBR. 1605, PG. 406
2.90' N OF E/W 1/4 LINE E 46.17' WEST OF
N/S 1/4 LINE

N 51.95' E 26.94' ESE 31.66' WNW 24.15'
11" POP. 11" POP. 8" POP. 30" BEECH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

FOUND 3/4" X 16" IRON PIPE ALONG SIDE A 3/4" ROD BEING 0.2' EAST OF PIPE

NORTH N 62° W E
52.08' 24.23' 26.90'
14" ASPEN 40" BEECH ASPEN

HISTORICAL USAGE, DOCUMENTATION & EVIDENCE OF CORNER LOCATION REVIEWED (RATIFIED BY MUSKEGON COUNTY PEER GROUP) SEPTEMBER 9, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP (REPLACED 3/4" X 16" IRON PIPE)

| | | | | | |
|-----------------------|-----------------------|-----------------------|--------------------|-----------------------|-----------------------|
| S 70° E | N 88° E | N 62° W | N 8° W | S 75° E | S 35° W |
| 31.60' | 26.90' | 24.23' | 52.08' | 7.52' | 33.84' |
| 12" ASPEN | 10" ASPEN | 40" BEECH | 14" ASPEN | 10" ASPEN | 10" ASPEN |
| (FD. NAIL SW'LY SIDE) | (FD. NAIL IN N. SIDE) | (FD. NAIL SW'LY SIDE) | (FD. NAIL W. SIDE) | (SET NAIL NE'LY SIDE) | (SET NAIL NW'LY SIDE) |

Signed by *Stephen Vallier*
Surveyor's Michigan License No. 28428

