

SURVEY & REMONUMENTATION

LIBER **1810** PAGE **565**

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECORDS & RECORDS

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 29 AM 10:13

For corners in

Muskegon
(County)

Located In:

Corner Code =#

Carrie Carter
REGISTER OF DEEDS

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>9</u> R <u>15</u> | <u>H-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

A1589

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephen V. Vallier, in a field survey on July, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO set 1/4 corner.
1980 Liber 1188 Page 209 Set "T" iron midway on line
1984 C.F. Lewandowski Liber 1297 Page 935 Found 1" Iron Pipe
Reset with 4" x 30" cast iron monument with County Cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" cast iron monument with County Survey Cap.
Origin undetermined - Accepted position of corner due to Historical usage and document.

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

July 5, 1994 SW

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" cast iron monument with County Survey Cap.

- S 55 deg E 65.21' 18" Maple with nail
- S 20 deg W 30.45' 14" Twin Maple with nail
- N 60 deg W 66.00' 24" Beech with nail
- N 15 deg W 47.55' 28" Beech with nail



Signed by *Stephen Vallier* Date *Dec 27, 1994*

Surveyor's Michigan License No. 28428