

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MUSKEGON (County)

Located In:

Corner Code #

- 1. Public Land Survey T 9N R 15W H-13
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

A 1543

STATE OF MICHIGAN
COUNTY OF MUSKEGON
REGISTER OF DEEDS
1994 DEC 27 AM 11:41

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, STEPHEN V. VALLIER in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO SET 1/4 SECTION POST
N 63° E 11 LINKS 8" HEMLOCK
N 13° W 6 LINKS 10" HEMLOCK

1983 D. SCHIELE, LBR. 1262, PG. 358
FOUND CAST IRON MON. IN MON. BOX
ENE 111.55' TWIN 20" MAPLE
SE 47.89' T. POLE
SW 63.53' TWIN 12" MAPLE
NW 66.96' 8" APPLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAST IRON MON. IN MON. BOX (H-1 OTTAWA COUNTY, T8N, R15W) ACCEPTED POSITION OF FOUND CORNER. APPEARS CORNER WAS SET BY SINGLE PROPORTIONATE MEASURE. HISTORICAL USAGE AND DOCUMENTATION AGREES WITH CORNER,

ENE 111.55' TWIN 20" MAPLE
SE 47.89' T. POLE
SW 63.53' TWIN 12" MAPLE
NW 66.96' 8" APPLE

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

July 5 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CAST IRON MON. IN MON. BOX WITH COUNTY SURVEY CAP

N 80° E 111.55' 20" TWIN MAPLE
SE 47.89' T. POLE
S 32° W 63.53' 12" TWIN MAPLE
N 20° W 66.96' 8" APPLE
N 64° W 79.37' Nail N side 6" Elm

Signed by [Signature]
Surveyor's Michigan License No. 28428
STEPHEN VALLIER
Land Surveyor
No. 28428

Date July 27, 1994