

LIBER 1744 PAGE 561

STATE OF MICHIGAN
COUNTY OF MUSKEGON
REGISTER OF DEEDS

1993 DEC 29 PM 4:03

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Carrie Carter
REGISTER OF DEEDS

For corners in

MUSKEGON

(County)

Located In:

Corner-Code //

1. Public Land Survey

T 9N R 15W I-5

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

**SURVEY &
REMONUMENTATION**

NOV 28 2000

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

SECTION

5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEPHEN V. VALLIER in a field survey on JULY 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO CORNER SET BY J. MULLETT, APR. 30, 1837

S 88° W S 23° E
4 LINKS 22 LINKS
12" BEECH 10" BEECH

IRON IN MONUMENT BOX-MUSKEGON CO. ROAD COMM.(REC. LBR 1002, PG 871-1976)

NE NW SW SE
93.41' 89.37' 121.03' 144.25'
TW. MAP. 6" PINE P. POLE P. POLE

WOOD STAKE-MCRC-1955

E NE NNE
57.64' 62.68' 73.30'
10" ELM 6" OAK 3" CHERRY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON PIPE IN MONUMENT BOX

NE NW SW SE
93.41' 89.00' 121.03' 144.25'
P. POLE 14" PINE P. POLE P. POLE

HISTORICAL USAGE, DOCUMENTATION & EVIDENCE OF CORNER LOCATION REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP JULY 7, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 20" CAST IRON MONUMENT W/ COUNTY SURVEY CAP IN MONUMENT BOX (REPLACED 1/2" IRON PIPE)

N 35°E N 25° W S 35°W S 75°E WEST WEST
93.41' 89.00' 121.03' 144.25' 123.03' 33.00'
TW. MAP. 14" TW. PINE P. POLE P. POLE G. & P. POLE FD. CAPPED IRON
(FD. NAIL) (SET NAIL) (FD. NAIL) (FD. NAIL) (SET NAIL) #18978

Signed by

Stephen Vallier
STEPHEN V. VALLIER

28428

Date

Dec 29, 1997

Surveyor's Michigan License No.