

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MUSKEGON (County)

Located In:

Corner Code # I-12

- 1. Public Land Survey T 9N R 15W
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

A1534

STATE OF MICHIGAN COUNTY OF MUSKEGON REGISTER OF DEEDS 1994 DEC 27 AM 11:41 Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. A dot is present at row 12, column K.

I, STEPHEN V. VALLIER, in a field survey on DECEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- APRIL 1837 GLO SET 1/4 SECTION - 6" HEMLOCK 1972 M.C.R.C. LBR. 1002, PG. 873
1950'S M.C.R.C. 1 1/2" IRON PIPE FD. 1 1/2" IRON-PLACED MON. BOX OVER
NNE 83.53' 7" POPLAR WNW 82.40' 8" POPLAR
NE 49.40' 8" MAPLE SW 108.34' 15" ASH
ENE 66.30' W. CHERRY 1983 D. SCHIELE, LBR. 1262, PG. 353
WSW 108.70' 10" PEPPER FOUND IRON PIPE IN MON. BOX
NE 64.14" 24" CHERRY
E 33.20' FENCE POST
SE 61.55' 7" SPRUCE
NW 75.50' 7" POPLAR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/4" IRON IN MON. BOX- ACCEPTED POSITION OF EXISTING CORNER DUE TO EXISTANCE OF OLDEST KNOWN DOCUMENTED WITNESSES

- NE 64.14' 24" W. CHERRY
SW 108.34' 15" ASH

June 7, 1994
POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- REPLACED FOUND 1 1/4" IRON WITH 2 3/4" X 20" CAST IRON MON. WITH COUNTY SURVEY CAP. SET WITHIN MON. BOX
N 50° W 75.50' NAIL S. SIDE 8" ASPEN
S 77° W 159.93' NAIL N. SIDE P. POLE
S 50° W 47.10' CONCRETE MONUMENT
S 33° E 61.59' NAIL W. SIDE 10" SPRUCE
EAST 33.20' STEEL FENCE POST
N 23° W 113.62' NAIL S. SIDE 8" TRIPLE ASH

Signed by [Signature] Surveyor's Michigan License No. 28428

Date June 27, 1994

