

REC'D

1993

LIB# 1744 PAGE 563

STATE OF MICHIGAN
COUNTY OF MUSKEGON
REGISTER OF DEEDS

1993 DEC 29 PM 4:04

COMMISSIONER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Carrie Carter
REGISTER OF DEEDS

For corners in

MUSKEGON

(County)

Located In:

Corner Code //

- 1. Public Land Survey T 9N R 15W J-6
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, STEPHEN V. VALLIER in a field survey on SEPTEMBER 9, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET BY GLO

SET UNCONCRETE MONUMENT C.F. LEWANDOWSKI 1971
(UNRECORDED)

S 55°W	N 53°W	N46°E	S 40°E
54.50'	53.35'	56.80'	40.30'
6" PINE	6" PINE	12" PINE	12" PINE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 4" X 4" X 36" CONCRETE MONUMENT (CONDITION BROKEN-POOR)

S 65° E
40.62'
12" PINE

FOUND CONCRETE MONUMENT SET AT INTERSECTION OF N-S AND E-W 1/2 LINES. HISTORICAL USAGE, DOCUMENTATION & EVIDENCE OF CORNER LOCATION REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP, SEPTEMBER 9, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP (REPLACED 4" X 4" X 36" CONCRETE MONUMENT)

S 70°E	N 40°E	N 62°E	S 65°E	S 15°E	N 0° E
2.05'	21.31'	45.02'	40.62'	36.44'	7.78'
4" OAK	16" R. PINE	12" R. PINE	12" R. PINE	12" R. PINE	4" X 4" WOOD FENCE POST
(SET NAIL N SIDE)	(SET NAIL SE'LY SIDE)	(SET NAIL N'LY SIDE)	(SET NAIL S'LY SIDE)	(SET NAIL E'LY SIDE)	(SET NAIL WITH TAG E'LY SIDE)

Signed by

Stephen V. Vallier
STEPHEN V. VALLIER

Date

Dec 28, 1993

Surveyor's Michigan License No.

28428