

APR 28 1995 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MUSKEGON

COMMISSION

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>9N</u> R <u>15W</u> | <u>J-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

A1540

STATE OF MICHIGAN
COUNTY OF MUSKEGON
REGISTERED FOR RECORD
DEC 27 AM 11:41
Doris Carter
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, STEPHEN V. VALLIER, in a field survey on SEPTEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO SET 1/4 CORNER
S 38° W 13 LINKS 10" BEECH
S 59° E 10 LINKS 10" HEMLOCK

1950'S M.C.R.C. 1 1/4" IRON BAR
NNW 43.0' MAPLE CLUSTER
NW 97.82' 12" MAPLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/2" X 18" IRON BAR - ACCEPTED POSITION OF FOUND CORNER - EVIDENCE APPEARS IT WAS SET BY SINGLE PROPORTIONATE MEASURE/FITS OCCUPATION ORIGIN UNKNOWN

SSE 44.98' MAPLE CLUSTER

Jan 7 1994
POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 30" CAST IRON MON. WITH COUNTY SURVEY CAP-REPLACED 1 1/2" IRON BAR
S 63° E 44.98' NAIL N. SIDE 30" MAPLE CLUSTER
S 8° W 42.00' NAIL W. SIDE FENCE POST
S 88° W 140.61' NAIL N. SIDE 30" MAPLE
N 79° W 87.01' NAIL S. SIDE 20" QUAD MAPLE
N 20° E 44.53' NAIL E. SIDE 22" R. PINE
N 60° E 51.18' NAIL S. SIDE 16" W. PINE
N 2° W 53.02' NAIL E. SIDE 6" ELM

Signed by _____

Date Jan 27, 1994

Surveyor's Michigan License No. _____

