

**SURVEY &
REMONUMENTATION**

LIBER **1810** PAGE **22**

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>MUSKEGON</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>9</u> R <u>15</u>	<u>J-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>9</u> R <u>15</u>	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 RECEIVED FOR RECORD
 1994 DEC 27 AM 11:40
 REGISTER OF DEEDS
Robin Carter
 Register of Deeds Stamp & File Number

A1529

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, STEPHEN V. VALLIER, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1" IRON IN MONUMENT BOX MUSKEGON COUNTY ROAD COMMISSION 1950
 PREVIOUSLY RECORDED IN LIBER 1277 PG. 85
 SW 110.4 18" CHERRY
 NW 47.62 8" POPLAR
 N 49.53 8" PINE
 NW 58.50 8" PINE
 NNE 68.5 8" POPLAR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 3/4 IRON PIPE OVER 3/4" X 2" PINCHED PIPE IN MONUMENT BOX
 S72°W 110.36 26" CHERRY (SET NAIL NW SIDE)
 N4°W 49.55 10" RED PINE (FOUND NAIL EAST SIDE)
 N15°W 47.55 8" ASPEN (FOUND NAIL WEST SIDE)

June 7, 1994 SL
 POSITION OF SAID
 RECORDED CORNER
 REVIEWED & RATIFIED
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 REPLACED FOUND IRONS WITH 2 3/4" X 20" CAST IRON MONUMENT WITH COUNTY SURVEYOR CAP.
 S72°W 110.36 26" CHERRY (SET NAIL NW SIDE)
 N4°E 49.55 10" RED PINE (FOUND NAIL EAST SIDE)
 N15°W 47.55 8" ASPEN (FOUND NAIL WEST SIDE)
 N55°W 79.39' 18" RED PINE (SET NAIL SOUTH SIDE)
 S80°E 324.74' 14" TWIN OAK (SET NAIL SOUTH SIDE)
 N40°W 58.47' 12" RED PINE (SET NAIL SOUTH WESTERLY SIDE)

Signed by *Stephen Vallier*
 Surveyor's Michigan License No. 28428

STATE OF MICHIGAN
 LAND SURVEYOR
 STEPHEN VALLIER
 No. 28428

Date Dec 24, 1994