

**SURVEY &
REMONUMENTATION**

LIBER **1810** PAGE **557**

APR 28 1995

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Muskegon
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|----------|---|-----------|------------|
| 1. Public Land Survey | T | <u>9</u> | R | <u>15</u> | <u>K-7</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

A 1581

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 RECEIVED FOR RECORD
 1994 DEC 29 AM 10:11
Carrie Carter
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephen V. Vallier field survey on July, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1837 Corner set by GLO
 1950's M.C.R.C. tie Map Iron Pipe
 1975 M.C.R.C. Liber 1064 Page 558 Found 1 1/2" Iron Pipe
 1984 C.F. Lewandowski Liber 1301 Page 589 Found 1 1/2" Iron Pipe replaced with 4" x 30" C.L. Monument with county survey cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 4" C.I. Monument/cap missing. Accepted position of corner due to Historical usage and consistent documentation.

POSITION OF SAID
 RECORDED CORNER
 REVIEWED & RATIFIED
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

Mar 1, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 4" Cast Iron Monument

- S 75 deg. E 72.53' 13" map with nail
- S 35 deg. W 49.25' Guy Pole with nail
- N 35 deg. W 48.20 USGS with nail
- N 35 deg. E Power Pole with nail



Signed by *Stephen Vallier* Date *Dec 27 1994*

Surveyor's Michigan License No. 28428