

**SURVEY &
REMONUMENTATION**

LIBER **1810** PAGE **559**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 RECEIVED FOR RECORD
 1994 DEC 29 AM 10:11
Doris Carter
 REGISTER OF DEEDS

For corners in

<u>Muskegon</u> <small>(County)</small>	Located In:	Corner Code #:
1. Public Land Survey	T <u>9</u> R <u>15</u>	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A1583

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, Stephen V. Vallier, in a field survey on November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1837 GLO set Section Corner
 1950's M.C.R.C. tie map 7/8" iron rod
 1982 C.F. Lewandowski Liber 1242 Page 317 Found 1" iron rod
 reset with 4" x 30" C.I. Monument with County Survey Cap.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 4" C.I. Monument with County Survey Cap
 Accepted position of corner due to historical usage and consistent documentation.

POSITION OF SAID
 RECORDED CORNER
 REVIEWED & RATIFIED
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

June 6 1994 su

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 4" Cast Iron Monument with County Survey Cap.

- S 75 deg W 52.96' 14" Stump
- S 50 deg E 118.25' Power Pole
- N 70 deg W 57.05' 4" Cherry
- N 55 deg W 34.56' 10" Aspen with Nail
- N 50 deg E 40.90' Fence Post with Nail



Signed by *Stephen Vallier* Date *Dec 27, 1994*
 Surveyor's Michigan License No. 28428