

SURVEY & REMONUMENTATION

LIBER **1810** PAGE **21**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MUSKEGON

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------------------|-------------|
| 1. Public Land Survey | T <u>9N</u> R <u>15W</u> | <u>L-10</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>25</u> T <u>9N</u> R <u>15W</u> | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

A1528

Carrie Carter
REGISTER OF DEEDS

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECORDATION RECORDS
1994 DEC 27 AM 11:40

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, STEPHEN V. VALLIER in a field survey on DECEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

IRON BY JOINER ENGINEERING, INC. NO WITNESSES

CORNER NOT SET BY GLO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND $\frac{1}{2}$ " CAPPED IRON ROD (#18987) AT INTERSECTION OF NORTH-SOUTH AND EAST-WEST 1/4 LINES

Oct 3, 1994
POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED $\frac{1}{2}$ " ROD WITH 2 3/4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEYOR CAP

- | | | |
|---------|--------|------------------------------------|
| S 8° W | 8.73' | 16" MAPLE (FOUND NAIL EAST SIDE) |
| N 12° W | 7.78' | 8" PEPPERIDGE (FOUND NAIL E. SIDE) |
| N 67° W | 24.81' | 24" CHERRY (FOUND NAIL S. SIDE) |
| S 89° E | 38.85' | 6" TWIN MAPLE (FOUND NAIL N. SIDE) |
| S 42° E | 24.96' | 12" ASH (FOUND NAIL NE'LY SIDE) |
| N 26° W | 29.38' | 10" W. PINE (FOUND NAIL E'LY SIDE) |

Signed by _____

[Signature]



Date _____

Dec 27, 1994

Surveyor's Michigan License No. _____

28428 Surveyor No. 28428