

**SURVEY &
REMONUMENTATION**

LIBER **1810** PAGE **545**

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

MUSKEGON
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>9</u> R <u>15</u> | <u>M-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

A1569

Carrie Woster
REGISTER OF DEEDS

1994 DEC 29 AM 10:10

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, STEPHEN V. VALLIER in a field survey on JULY, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO SET 1/4 POST
1985 C.F. LEWANDOWSKI, LIBER 1320, PAGE 474 CORNER OBLITERATED
RESET BY MUSKEGON COUNTY ROAD COMMISSION, WITNESSES - SET 4" x 30"
CAST IRON MONUMENT WITH COUNTY SURVEYOR CAP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" CAST IRON MONUMENT 1" DEEP
ORIGIN OF RECENT POSITION AND WITNESS UNCERTAIN. ACCEPTED POSITION OF CAST IRON MONUMENT AS RECORDED LIBER 1320, PAGE 474. EVIDENCE PRESENTS POSITIONED BY GOVERNMENT MEASURE.

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

Mar 1, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 4" x 30" CAST IRON MONUMENT - 1' DEEP
E 82.40' NAIL IN POWER POLE
S20 DEGREES E 58.76 NAIL IN 36" OAK
S85 DEGREES W 68.62 NAIL IN POWER POLE
SOUTH 2653.74 TO S.E. CORNER SECTION 1
NORTH 2650.12 TO N.E. CORNER SECTION 1



Signed by *Stephen Vallier*

Date *Mar 27, 1994*

Surveyor's Michigan License No. 28428