

**SURVEY &  
REMONUMENTATION**

LIBER **1810** PAGE **546**

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in  
MUSKEGON  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 1. Public Land Survey T 9 R 15 M-3  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*A1570*

*Carrie Carter*  
REGISTER OF DEEDS

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD  
1994 DEC 29 AM 10:10

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEPHEN V. VALLIER in a field survey on JULY, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 1837 GLO SET SECTION CORNER  
 1950's MUSKEGON COUNTY ROAD COMMISSION IRON PIPE  
 1985 C.F. LEWANDOWSKI LIBER 1320, PAGE 472  
 SET 2 3/4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2 3/4" x 30" CAST IRON MONUMENT WITH COUNTY SURVEYOR CAP  
 ACCEPTED POSITION OF EXISTING MONUMENT AS RECORDED IN LIBER 1320,  
 PAGE 472, DUE TO HISTORICAL USEAGE AND CONFIRMATION OF DOCUMENTATION.

*Mar 1, 1994 svv*

POSITION OF SAID  
 RECORDED CORNER  
 REVIEWED & RATIFIED  
 BY MUSKEGON COUNTY  
 PEER GROUP IN ACCORDANCE  
 WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2 3/4" x 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP  
 S30 DEG. E 61.86' FENCE CORNER  
 S25 DEG. W 73.26' TELEPHONE POLE  
 WEST 2652.04' DISTANCE TO SOUTH 1/4 CORNER SECTION 1



Signed by *Lyth Vallier* Date *Dec 27, 1994*  
 Surveyor's Michigan License No. 28428