

**SURVEY &
REMONUMENTATION**

LIBER 1810 PAGE 547

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**
MUSKEGON
(County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>9</u> R <u>15</u> | <u>M-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

A 1571

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 RECEIVED FOR RECORD
 1991 DEC 29 AM 10:10
Carrie Carter
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, STEPHEN V. VALLIER, in a field survey on JULY, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 GLO SET 1/4 CORNER
- 1900's GTWRR MAP IRON IN CENTER OF RAIL ROAD
- 1970's MUSKEGON COUNTY ROAD COMMISSION TIE BOOK 1 1/2" IRON PIPE NORTH OF CENTER LINE OF RAIL ROAD
- 1985 C.F. LEWANDOWSKI, LIBER 1320, PAGE 470 FOUND IRON PIPE SET CAST IRON MONUMENT WITH COUNTY SURVEY CAP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" x 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP (1' DEEP) ACCEPTED POSITION OF CORNER DUE TO PROXIMITY OF SINGLE PROPORTIONATE MEASURE. HISTORICAL USAGE HAS BEEN TO THIS CORNER. NO DOUBLE CORNER FOUND AT CENTER LINE OF RAIL ROAD. THIS POSITION WOULD DISTURB SECTION.

POSITION OF SAID
 RECORDED CORNER
 REVIEWED & RATIFIED
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

Mar 11, 1994 SW

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 4" x 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP (1' DEEP)
- N20 DEG. 108.60' NAIL IN POWER POLE
- S10 DEG. E 136.60' NAIL IN POWER POLE
- SOUTH: 194.60' CENTER LINE ABANDONED RAIL ROAD TRACK
- SOUTH 2641.37' SOUTH EAST CORNER SECTION 12
- NORHT 2652.08' NORTH EAST CORNER SECTION 12



Signed by *Stephen Vallier* Date *Dec 27, 1994*
 Surveyor's Michigan License No. 28428