

**SURVEY &  
REMONUMENTATION**

APR 28 1995

LIBER **1810** PAGE **551**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Muskegon  
(County)

Located In:

Corner Code #

- |                                       |                         |            |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey                 | T <u>9</u> R <u>15</u>  | <u>M-8</u> |
|                                       | T _____ R _____         | _____      |
|                                       | T _____ R _____         | _____      |
|                                       | T _____ R _____         | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____      |
|                                       | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____      |
|                                       | S _____ T _____ R _____ | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                         |            |
| 5. Private Claims _____               |                         |            |

*A1575*

*Janice Carter*  
REGISTER OF DEEDS

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD  
1994 DEC 29 AM 10:10

Register of Deeds Stamp & File Number

I, Stephen V. Vallier a field surveyor on Nov, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 GLO set quarter corner
- 1984 C.F. Lewandowski L. 1301 P. 591 found 5/8 rod on top of 1 1/2" Iron Pipe. Reset 4" x 30" Cast Iron Monument with County survey Cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" Cast Iron Monument with survey cap. Accepted position of existing corner due to Historical use and known document. Origin of perpetuated monument uncertain.

*Oct 4, 1994*

POSITION OF SAID  
RECORDED CORNER  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 4" Cast Iron Monument with survey cap.
- S 15 deg. E 86.30' Nail in 14" Cherry
- S 10 deg. W 60.70' Nail in 8" Aspen
- N 20 deg. W 65.40' Nail in 8" Pine
- S 85 deg E 35.97 Nail in Power Pole



Signed by *Stephen Vallier* Date *Dec 27, 1994*

Surveyor's Michigan License No. 28428