

**SURVEY &  
REMONUMENTATION**

LIBER **1810** PAGE **556**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

APR 28 1995

For corners in

MUSKEGON COMMISSION Located In: \_\_\_\_\_  
(County)

Corner Code =# \_\_\_\_\_

- |                                       |   |          |   |           |             |
|---------------------------------------|---|----------|---|-----------|-------------|
| 1. Public Land Survey                 | T | <u>9</u> | R | <u>15</u> | <u>M-13</u> |
|                                       | T | _____    | R | _____     | _____       |
|                                       | T | _____    | R | _____     | _____       |
|                                       | T | _____    | R | _____     | _____       |
| 2. Property Controlling<br>in Section | S | _____    | T | _____     | _____       |
|                                       | S | _____    | T | _____     | _____       |
| 3. Miscellaneous<br>Property in Sec.  | S | _____    | T | _____     | _____       |
|                                       | S | _____    | T | _____     | _____       |

*A1580*

STATE OF MICHIGAN  
 COUNTY OF MUSKEGON  
 RECEIVED FOR RECORD  
 1994 DEC 29 AM 10:11  
*Carrie Carter*  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEPHEN V. VALLIER, in a field survey on NOVEMBER, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 GLO SET SECTION CORNER
- 1950'S MUSKEGON COUNTY ROAD COMMISSION TIE MAP NO DESCRIPTION -WITNESS ONLY
- 1982 C.F. LEWANDOWSKI FOUND RAILROAD SPIKE ON TOP OF "T" IRON  
LBR. 1242 PG. 297 - RESET WITH 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEY CAP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND 4" CAST IRON MONUMENT
- ACCEPTED POSITION OF CORNER - CONSISTANT WITH EVIDENCE OF KNOWN DOUCMENTATION


*Nov 8, 1994 sw*

POSITION OF SAID  
 RECORDED CORNER  
 REVIEWED & RATIFIED  
 BY MUSKEGON COUNTY  
 PEER GROUP IN ACCORDANCE  
 WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" CAST IRON MONUMENT WITH COUNTY SURVEY CAP

- N 10° EAST 164.25'
- N 20° WEST 147.70' P. POLE
- S 40° WEST 92.50' P. POLE
- S 20° WEST 101.65' P. POLE
- N 30'+ CENTERLINE ROAD



Signed by *Stephen Vallier* Date Dec 27, 1994  
 Surveyor's Michigan License No. 28428