

SURVEY & REMONUMENTATION

LIBER **2052** PAGE **592**

APR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1997 DEC 30 PM 3:21

Carris Carter
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in
Muskegon **SECTION**
(County)

Located In: Corner Code #

1. Public Land Survey	T	9N	R	16W	E-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Stephen V. Vallier P.S. November 4, 97

I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837	G.L.O. Set Post	J. Mullett		
	North 06° West	10 Links	20 Inch Beech	
	North 81° West	08 Links	22 Inch Hemlock	
1885	L.C.R.C. Liber 1230, Page 477		D. Schiele	Found 2/3 Inch Iron Pipe
1987	L.C.R.C. Liber 1411, Page 543		R. VanRiper	Found 3/4 Inch Iron Pipe
	Reset with 4 Inch By 30 Inch Cast Iron Monument With County Surveyor Cap.			
	North 11° East	48.15 Feet	10 Inch Pine	Found Spike
	South 28° East	33.49 Feet	Telephone Pole	Found Spike
	South 17° East	28.05 Feet	U.S.G.S. Monument	
	North 25° West	58.10 Feet	16 Inch Pine	Found Spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4 Inch By 30 Inch Cast Iron Monument with County Surveyor Cap.				
Historical Usage and Known Documentation Supports Position of Corner.				
Source and Origin Undetermined				
	North 11° East	48.15 Feet	10 Inch Pine	Found Spike
	South 28° East	33.49 Feet	Telephone Pole	Found Spike
	South 17° East	28.05 Feet	U.S.G.S. Monument	
	North 25° West	58.10 Feet	16 Inch Pine	Found Spike

POSITION OF SAID RECORDED CORNER REVIEWED & IDENTIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

SVV
11/4/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 4 Inch by 30 Inch Cast iron Monument With County Surveyor Cap.				
	North 11° East	48.15 Feet	10 Inch Pine	Found Spike
	South 28° East	33.49 Feet	Telephone Pole	Found Spike
	South 17° East	28.05 Feet	U.S.G.S. Monument	
	North 25° West	58.10 Feet	16 Inch Pine	Found Spike



Signed by *Stephen V. Vallier* Date December 15, 1997
Surveyor's Michigan License No. 28428

A1911