

MAR 0 6 1998

1 IREP 2052 PAGE 584

- *	Commen
STATE OF	HICHIGAN
OOOHA LIFE	売付けノベスティー
RECEIVED	OF OFTOIR

SECTION

Private Claims _

Lot No.

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

1997 DEC 30 PM 3: 10

Lavier.		
EFFITTER	OF DEEDS	א שימשים

or corners in		
Muskegon (County)	Located In:	Corner Code #
Public Land Survey		M 13
	T R T R	
	T R	
2. Property Controlling	g SR	
in Section	S T R	_ _
3. Miscellaneous	S T R	
Property in Sec.	S T R	

__ , Recorded Plat __

Register of Deeds Stamp & File Number

. Ralph W VanRiper, in a field survey on	Nov. 4	
to hereby certify that under requirements of P.A. 74, Mic	chigan P.A. of 1970, the c	corner points mentioned
n lines 1 and 2 above were in conformance with regi	ulations and rules there	elore as required in the
current manual of survey instructions of the United Sta	ates Department of the I	Interior, Bureau of Land
Management or by a decree of a Court of Law and/or tha	at the corner points ment	tioned in lines 3, 4 and 5
above were in conformance with the rules of the Michig	an Board of Land Surve	eyors or by a Decree of a
Court of Law; established, re-established, monume	ented, re-monumented	, recovered, found as

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

11 12

Section Corner common to Sections 1 T9N R17W, 36 T10N R17W, 31 T10N R16W & 6 T9N R16W Post set by GLO Surveyors in 1837; W Oak 20" S37°W 46L and Pine 10" N74°W 19L . MCRC, 1950's Witness Map: NE 48.05' P.P.; SE 44.05' P.P.; WSW 102.52' P.P.; NNW 45.9' CB Head MCRC, Current Witness Book: 1" Pipe in Conc. in Mon. Box, Recorded L-1240, P-527 NE 58.87' P.P.; NW 61.92' Light Pole; SW 77.47' P.P.; WSW 102.52' P.P.; NNW 45.9' NE CB head

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

LCRL Recorded by C F Lewandoski; L-1240 P-527; 1" iron pipe in concrete in monument box N 44° E 58.87' Utility Pole; N43°W 61.92' L. Pole; S 73°W 77.47' P. Pole

Found 1" Pipe in Concrete in Monument Box Accepted corner based on historical usage and documentation

> RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990


POSITION OF SAID

5/12/97

2. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

 $\mathbf{1}^{\mathrm{nr}}$ Pipe in Concrete in Monument Box

N 74° E 63.421 Set PK Nail in NW side of Power Pole S 71° E 98.891 Set PK Nail in N side of Power Pole S 18° E 101.23 Set PK Nail in W side of Power Pole S 29° W 86.21' Center of Top Bolt of Fire Hydrant S 66° W 77.391 Set PK Nail in NW side of Power Pole N 43° W 61.84 Found Spike in NE side of Light Pole



signed by Melle Willia Ti			,		
Signed by	ala	Date De	ec. 26,	1997	• • •
			 -		
Surveyor's Michigan Licenses No.	160/6				