LIBER 3121 PAGE 642

LAND CORNER RECORDATION CERTIFICATE

.369	
STATE OF MI	
COUNTY OF MU	
RECEIVED FOR	RECORD

Filing Requirement of Act 74, Mich. P.A. 1970 200 DEC 20 PM 1: 48 For corners in Muskegon Located In: Corner Code # (County) 1. Public Land Survey T<u>9N_R14W</u> TiON RIYW TION R 2. Property Controlling SURVEY & in Section remonumentation 3. Miscellaneous Property in Sec. Register of Deeds Stamp & File Number JAN <u>31 2001</u> ____, Recorded Plat _ SECTION 5. Private Claims _, in a field survey on _ November 14 , 20<u>00</u> do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below: NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate A. Description of original monument and accessories and/or subsequent restoration: John Mullett (G.L.O.) set post corners in Towns 9 and 10 North, Ranges 13 and 14 West. 1837 N 27° W 18" Pine 50 Links **VALLIER** S 87° W 10" Beech 24 Links Land Surveyor 1885 Old County survey records, Page 23, note section corner being re-established: No, N 22° W 12" Maple 8 1/2 Links 28428 N 53° E 14" Hemlock 15 Links S 49° E 18" Maple 7 1/2 Links 1968 Consumers Power Company (No. S-F 16758) shows distance from L-1 to M-1 as 2602.0'. No witnesses. 1982 C. F. Lewandowski found a 1" iron pipe and reset with a 4" x 32" cast-iron monument with a "County Surveyor Legend." Recorded L.C.R.C. in Liber 1242, Page 310. S 70.23 Power Pole S 60° 59.05 \mathbf{E} 8" Oak 70° N W 12,80 8" Cherry N 25° W 34.61 10" Cherry Description of corner evidence found and/or method applied in restoring or reestablishing corner: A 4" x 32" cast-iron monument with "County Surveyor Legend" was found. Fence lines to South and West. Witnesses check with L.C.R.C. Liber 1242, Page 310. Position of the existing corner accepted due to historical usage and documentation. Description of monument for corner and accessories established to perpetuate locating the position of the corner: A 4" x 32" cast-iron monument with a" County Surveyor Legend" was found. Fence Corner is 0.5' North and 1.7' East. N 25° E 61.50 Power Pole Set 20D nail in E side 70° E 109.821 26" Maple Set 20D nail in N side POSITION OF SAID Roteful S 70.231 Power Pole Found nail in W side RECORDED CORNER 10/17/00 07° S 52.731 8" Aspen Stump found nail in W side REVIEWED & RATIFIED 82° W BY MUSKEGON COUNTY Ν 23.96 18" Tri Cherry Found nail in W side 25° 34.60' 18" Tri Cherry Found nail in W side PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990 Signed by 19/00 Surveyor's Michigan License No.

REVISED MAY 14, REVISED JAN., REVISED OCT... AAIIA

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28,