

SURVEY & MONUMENTATION

MAR 06 1998

LISEP 2050 PAGE 790

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

A1877

1997 DEC 22 PM 3:06

Carrie Carter
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION
 Muskegon County

Located in: Corner Code

#

1. Public Land Survey
 T 10N R 17W E-4
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald G. Sandel, in a field survey on July 7, 1997 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.



- A. Description of original monument and accessories and/or subsequent restoration:
- (1) GLO: Set Quarter Section Post, June 01, 1837
 Pine 24" N37°W 0.15 chains
 W.Oak 6" S61°E 0.23 chains
 - (2) LCRC Liber 1207, page 644, D. Schiele #23517, found 1" carriage bolt
 NE 8" Oak 33.76
 SE 8" Oak 12.26
 SW 10" Oak 19.70
 NW 12" Oak 25.34

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (1) Found 1" carriage bolt 18" long at center of a North/South trail. Used existing witnesses to verify corner location.
 - (2) Historical usage, documentation, and evidence of corner location reviewed and ratified by the Muskegon County Peer Group, June 16, 1997.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set 3"D x 31" Cast Iron "County Survey" Monument in place of found 1" carriage bolt; witnessed as follows:
- N21°E Set Nail SW side 5" Oak 25.87'
 - N52°E Set Nail SE side 5" Oak 7.13'
 - S60°E Found Nail N. side 10" Oak 12.30'
 - S20°W Set Nail NW side 5" Oak 16.90'
 - S70°W Found nail SE side 10" Oak 19.73'
 - N52°W Set Nail S. side 12" Oak 25.13'

POSITION OF SAID
 RECORDED CORNER
 REVIEWED & RATIFIED
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

Signed by Donald G. Sandel Date 5 December 1997
 Surveyor's Michigan License No. 25870