

MAR 06 1998

LINE 2052 PAGE 571

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1997 DEC 30 PM 3:09

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>17W</u>	<u>G 12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Carris Carter
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Ralph W VanRiper, in a field survey on Oct. 30, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter Corner between Sections 33 and 34, T10N R17W

Post set by GLO Surveyors in 1837: Blk Oak 8" S57°W 23L and Blk Oak 7" N86°E 14L

MCRC, 1950's Witness Map and Current Witness Book does not included this area.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rod

Have record that E H Peck; M M Buck and F F Smith used this corner

Accepted corner based on historical usage and documentation

POSITION OF SAID
RECORDED CORNER
REVIEWED & CARRIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

6/3/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap

- N 20° E 11.49' Found Spike in E Side of 6" Oak
- S 80° E 10.89' Found Spike in S Side of 14" Oak
- S 25° E 16.19' Found Spike in S Side of 18" Oak
- S 34° W 30.23' Found Spike in NW Side of 18" Oak
- West 35.50' Found Spike in N Side of Twin 8" Oak
- N 19° W 26.80' Found Spike in SW Side of 18" Oak



Signed by Ralph W. Van Riper

Date Dec. 26, 1997

Surveyor's Michigan License No. 16946

A1892