

SURVEY & REMONUMENTATION

LIBER 1952 PAGE 820

STATE OF MICHIGAN
COUNTY OF MUSKOGEE

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 21 1997

MAR 23 1997 10:48

For corners in
Muskegon
(County)

COMMISSION

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 10N. R 17W. | L-2 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Commissioner
MUSKOGEE COUNTY
A1846

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stanley H. Shackelford, P.S. in a field survey on October 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837-GLO NOT SET			
1950s-M.C.R.C. CORNER NOT IDENTIFIED	WEST	34.32	6" BLACK OAK
	NORTHEAST	38.35'	POWER POLE
	EAST	31.95	FENCE POST
DISTANCE 2645.50' SOUTH			
DISTANCE 3999.90' NORTH	NORTHEAST	38.35	POWER POLE
NO DATE - WILLIAMS & WORK IRON	SOUTHWEST	44.60'	TELEPHONE POLE
	WEST	34.30'	26" OAK
	NORTHWEST	66.70'	4" ELDER

SEE ATTACHED "EXHIBIT L-2"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEYOR LEGEND IN ASPHALT.

WEST	34.31'	24" OAK	FOUND SPIKE
SOUTH 66° EAST	40.22'	8" TWIN MAPLE	
NORTH 56° EAST	38.32'	POWER POLE	
SOUTH 33° WEST	44.60'	TELEPHONE POLE	

CHECKS WITNESSES. CHECKS 1950s DISTANCES NORTH AND SOUTH. CHECKS INTERSECTION OF QUARTERLINE WITHIN 6± EAST AND WEST.

POSITION OF SAID RECORDED CORNER REVIEWED & CONFIRMED BY MUSKOGEE COUNTY WITH P.A. 345, OF 1990
sw 8/13/96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEYOR LEGEND IN ASPHALT.

WEST	34.31'	24" OAK	FOUND SPIKE
SOUTH 66° EAST	40.22'	8" TWIN MAPLE	FOUND SPIKE
NORTH 56° EAST	38.32'	POWER POLE	FOUND SPIKE
SOUTH 33° WEST	44.60'	TELEPHONE POLE	FOUND SPIKE



Signed by Stanley H. Shackelford
Surveyor's Michigan License No. 30100

Date 12-26-96

LIBER 1952 PAGE 820

A1846 *gud*

EXHIBIT L-2

LIBER 1952 PAGE 821

1985 LIBER 1322, PAGE 623 BY C.F.L.

FOUND 5/8" IRON ROD - SET 4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEYOR LEGEND

WEST	34.31'	24" OAK
NORTH 56° EAST	38.32'	POWER POLE
SOUTH 66° EAST	40.22'	8" TWIN MAPLE
SOUTH 33° WEST	44.60'	TELEPHONE POLE