

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

173 OCT 30 AM 9:48

For corners in
MUSKEGON
(County)

Located In: Corner Code #

- 1. Public Land Survey T 10N R 17W L4
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

SURVEY &
DOCUMENTATION
FEB 01 1999

2011
A1848

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____ SECTION _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	7	8	9	10	11	12	13	14	15	16	17
3												
4	7	8	9	10	11	12	13	14	15	16	17	18
5												
6	10	11	12	13	14	15	16	17	18	19	20	21
7												
8	13	14	15	16	17	18	19	20	21	22	23	24
9												
10	16	17	18	19	20	21	22	23	24	25	26	27
11												
12	19	20	21	22	23	24	25	26	27	28	29	30
13												

I, Stephen V. Vallier, P.S., in a field survey on October 30, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3 and 4 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration


- 1955 CORNER NOT SET BY G.L.O. WM. DEVETTE SURVEY CENTER OF SECTION FOUND RETRACED SOUTH 1/4 LINE TO BEAR LAKE NO WITNESSES
- 1960 F.F. SMITH SURVEY MISCELLANEOUS SURVEYS AT TRANSAMERICA TITLE SHOW DISTANCE - EAST 1/4 CORNER TO CENTER SECTION
- 1985 C.F. LEWANDOSKI RECORDED L.C.R.C. LIBER 1322, PAGE 626 SET COUNTY SURVEY MONUMENT

NORTH 28° WEST 43 93' 26" OAK
 NORTH 11° EAST 38 36' 20" OAK
 SOUTH 63° EAST 68 39' POWER POLE
 SEE ATTACHED EXHIBIT "L-4"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner

FOUND 2 3/4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEYOR CAP. HISTORICAL USAGE AND DOCUMENTATION OF RECORD SUPPORT LOCATION OF CORNER. SOUTH 1/4 CORNER (L-5) IS IN BEAR LAKE AND NEVER SET BY G.L.O. IT APPEARS THAT CENTER OF SECTION WAS ATTEMPTED TO BE SET AT MEAN BEARING OF THE EAST AND WEST LINE OF SECTION. ACCEPTED POSITION OF EXISTING CORNER DUE TO HISTORICAL USAGE AND DOCUMENTATION OF RECORD.

POSITION OF SAID RECORDED CORNER REVIEWED AND FOUND BY MUSKEGON COUNTY PLAT AND INSTRUMENTANCE WITH P.A. 345, OF 1970



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

FOUND 2 3/4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEYOR CAP LOCATED IN MONUMENT BOX.

NORTH 28° WEST 43 93' 26" OAK FOUND SPIKE
 NORTH 11° EAST 38 36' 20" OAK FOUND SPIKE
 SOUTH 63° EAST 68 39' POWER POLE FOUND SPIKE
 SOUTH 05° WEST 33 15' CONCRETE MONUMENT
 WEST 2689 68' WEST 1/4 CORNER
 EAST 2711 55' EAST 1/4 CORNER

Signed by Stephen V. Vallier
 Surveyor's Michigan License No. 28328

Date Dec 27 1996

1952 PAGE 824

EXHIBIT L-4

1989 SOUTH 33 15' CONCRETE MONUMENT
D SCHIELE RECORDED SURVEY LIBER 1549, PAGE 970
1992 D SANDEL SURVEY RECORDED LIBER 1631, PAGE 378
1993 PLAT OF SHERWOOD FOREST NO 6 REFERENCED TO CENTER OF SECTION L-4

SURVEY &
REMONUMENTATION

FEB 01 1999

SECTION