

SURVEY & REMONUMENTATION

APR 03 1998

LIBEP 2052 PAGE 577

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1997 DEC 30 PM 3:09

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>17W</u>	<u>L 12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Carrie Carter
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35								
13													

I, Ralph W VanRiper, in a field survey on Oct 30, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in-conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Center of Section 36 T10N R17W
Not Set by GLO Surveyors

MCRC, 1950's Witness Map and Current Witness Book does not included this area.

Survey recorded by S Barnett, L 1039, P789, Found cluster of 4 nails in Centerline of Hackley and Parslow; 14" Maple S49°W 47.78'; P.P. S 39°E 34.30'; P.P. N 41°E 37.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found PK Nail with Survey Cap, Witness on Survey by S Barnett L 1039, P789

Have records that M M Buck, F F Smith, C F Lewandoski and D G Sandel using this corner.

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap

- N 30° E 106.50' Set Spike in E Side of 10" Elm
- N 72° E 54.85' Set Spike in SE Side of 14" Elm
- S 22° E 34.39' Found Spike in E Side of Power Pole
- S 69° W 87.33' Set Spike in SE Side of 24" Maple
- N 34° W 42.28' Found Spike in NE Side of Power Pole
- N 07° W 96.50' Set Spike in W Side of 14" Maple



Signed by Ralph W. Van Riper Date Dec. 24, 1997
Surveyor's Michigan License No. 16946

A1898