

**SURVEY & REMONUMENTATION**

LIBEP **1952** PAGE **816**

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECORDS & DEEDS

MAR 21 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

1996 DEC 30 AM 8:48

For corners in  
Muskegon  
(County)

**COMMISSION**

Located In: Corner Code #

- |                                       |                           |            |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey                 | T <u>10N</u> R <u>17W</u> | <u>M-4</u> |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                           |            |
| 5. Private Claims _____               |                           |            |

*Carr Carter*  
RECORDER OF DEEDS

A1844

Register of Deeds Stamp & File Number

I, Stanley H. Shackelford, P.S. in a field survey on October 30, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
1837 G.L.O. SET CORNER SOUTH 29° WEST 27 LINKS 20" HEMLOCK  
NORTH 33° WEST 34 LINKS 20" HEMLOCK

1950's M.C.R.C. CORNER NOT MENTIONED

SOUTHWEST 46.50' CENTER OF IRON STREET SIGN  
2711.54' TO CENTER SECTION  
EAST 17.55' WEST END OF HEAD WALL  
**SEE ATTACHED "EXHIBIT M-4"**

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2 3/4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEYOR LEGEND IN MONUMENT BOX.

NORTH 10° WEST 92.06' TELEPHONE POLE  
SOUTH 42° EAST 37.29' POWER POLE  
SOUTH 21° WEST 63.54' TELEPHONE POLE  
SOUTH 51° WEST 102.82' NE CORNER HOUSE


CHECKS WITH POSITION OF HISTORICAL USAGE.  
CHECKS WITH 1950's MEASURE TO WEST.

POSITION OF SAID  
RECORDED CORNER *sv 4/10/96*  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 2 3/4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEYOR LEGEND IN MONUMENT BOX.

NORTH 10° WEST 92.06' TELEPHONE POLE FOUND SPIKE  
SOUTH 42° EAST 37.29' POWER POLE FOUND SPIKE  
NORTH 21° WEST 63.54' TELEPHONE POLE FOUND SPIKE  
SOUTH 51° WEST 102.82' NE CORNER HOUSE



Signed by *Stanley Shackelford*

Date 12-26-96

Surveyor's Michigan License No. 30100

A1844

LIBEP **1952** PAGE **816**

EXHIBIT M-4

LIBER 1952 PAGE 817

1961-M.C.R.C. WITNESS BOOK

SOUTHWEST 65.80'  
 NORTHWEST 46.35'  
 EAST-NORTHEAST 19.55'

TELEPHONE POLE  
 TELEPHONE POLE  
 POWER POLE

1975-LIBER 1057, PAGE 142 BY F. SMITH

NORTH/NORTHWEST 49.35'  
 EAST/NORTHEAST 19.55'  
 SOUTH/SOUTHWEST 63.70'

TELEPHONE POLE  
 POWER POLE  
 TELEPHONE POLE

1985-LIBER 1322, PAGE 24, BY C.F.L. FOUND 1/2" ROD IN MONUMENT BOX. SET 2 3/4" X 30" CAST IRON MONUMENT WITH COUNTY SURVEYOR LEGEND IN MONUMENT BOX.

NORTH 10° WEST 92.06'  
 SOUTH 42° EAST 37.29'  
 SOUTH 21° WEST 63.54'  
 SOUTH 51° WEST 102.82'

TELEPHONE POLE  
 POWER POLE  
 TELEPHONE POLE  
 TO NE CORNER HOUSE