

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 RECEIVED FOR RECORD

For corners in

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>15W</u> <u>B-11</u>	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling In Section	S _____ T _____	SURVEY & REMONUMENTATION
	S _____ T _____	
3. Miscellaneous Property in Sec.	S _____ T _____	<u>NOV 28 2000</u>
	S _____ T _____	
4. Lot No. _____	Recorded Plat <u>SECTION</u>	
5. Private Claims _____		

1998 DEC 28 PM 3:37
Carrie Carter
 REGISTER OF DEEDS
LIBER 2189 PAGE 264
 Register of Deeds Stamp & File Number

I, Stephen V. Vallier, in a field survey on December 5, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1837** G.L.O. set corner.
 S 64° W 40 Links 20" Pine
 N 19° E 75 Links 30" Pine
- 1930's** T. Norlin measured South line of Section 30, C-11 to B-11, which equals 2,646.30' and B-11 to A-11, equaling 2,709.60'. No mention of what was found as monument.
- 1983** C. F. Lewandowski found a "T" iron and recorded in L.C.R.C., Liber 1263, page 291. Reset with cast-iron monument with county surveyor's cap.
 N 45° W 40.11' 12" White Oak
 N 30° E 37.28' 10" White Oak
 S 40° E 66.95' 10" Black Oak
 S 60° W 120.05' 24" White Oak

Nov 9, 1998
 POSITION OF SAID
 RECORDED CORNER
 REVIEWED & RATIFIED
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 4" cast-iron monument with county surveyor's cap on occupation lines, North and South. Accepted the position of corner based on historical usage and documentation. Corner also checks G.L.O. proration for position.
 N 45° W 40.11' 12" White Oak
 N 30° E 37.28' 10" White Oak
 S 40° E 66.95' 10" Black Oak

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 4"x30" cast-iron monument with county surveyor's cap.
 N 45° W 40.11' 12" White Oak Nail set in South side
 N 30° E 37.28' 10" White Oak Nail set in East side
 S 40° E 66.95' 10" Black Oak Nail set in North side
 S 35.95' Power Pole Nail set in West side



Signed by Stephen V. Vallier Date Dec 23, 1998
 Surveyor's Michigan License No. 28428

A 1981