

SURVEY & REMONUMENTATION

FEB 01 1999

LINE 1744 E 216

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1993 DEC 29 PM 12:57

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
Muskegon
(County)

Located In: Corner Code -##

- | | | |
|------------------------------------|---------------------------|--------------------|
| 1. Public Land Survey | T <u>11N</u> R <u>17W</u> | <u>E-2</u> |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>Seg. # 1 pm</u> |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

Conrad C. ...
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Donald G. Sandel November 17 1993

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO set quarter section post June 16, 1837
W. Oak 6" N57°E 0.21 ch
W. Oak 9" N13°W 0.22 ch
- No MCRC (1950's) witnesses on record for this corner (1950) or other information to our knowledge:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Set corner as lost 1/4 post by single proportion method - no occupation evidence.
- Historical usage, documentation, and evidence of corner location reviewed and ratified by Muskego County Peer Group November 16, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" x 20" cast iron "County Survey" monument witnessed as follows:

- S 9°E, set, nail E side with 3 blaze marks, 8" Oak, 33.37'
- S 37°W, set, nail NW side with 3 blaze marks, 10" Oak, 20.23'
- N 34°W, set, nail S side with 3 blaze marks, 10" Oak, 18.21'
- N 67°E, set, nail S side, 5" Pine, 14.21'
- N 86°W, set, nail S side, 14" W. Oak, 34.90'
- S 27°W, set, nail NE side 6" W. Oak, 44.92'

Signed by Donald G. Sandel Date 29 December 1993
Surveyor's Michigan License No. 25870