

APR 04 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Muskegon

(County)

Located In:

Corner Code

1. Public Land Survey

T 11N R 16W

C 7

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Ralph W VanRiper in a field survey on July 11, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to Sections 17, 18, 19 and 20, T 11 N, R 16 W, Dalton Township, Post set by GLO Surveyors in 1837 (B Ash 20", S 18° W, 22L) (B Ash 10", S 68° W, 16L)
MCRC (1950's) 3/4" Iron Pipe with 4 Witnesses
MCRC Witness Book, 5/8" Iron Pipe with 8 Witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 5/8" Steel Rod over a Plow Point in Asphalt pavement at the intersection of Automobile Road and Riley-Thompson Road. Verified corner location with existing witnesses.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4 Cast Iron Monument with County Survey Cap in Asphalt Pavement

- N 30° E 52.22' Set Spike in SE side of 8" Pine
- S 60° E 94.88' Set Spike in NE side of 6" Pine
- S 22° E 79.85' Found Spike in NE side of Power Pole
- S 65° W 51.12' Found Spike in NW side of 20" Oak
- S 70° W 64.40' Set Spike in NW side of 20" Oak
- N 40° W 41.40' Found Spike in SW side of 24" Oak



Signed by Ralph W. VanRiper
Surveyor's Michigan License No. 16946

Date Dec. 19, 1995