

R1871 p. 574 A1708

STATE OF MICHIGAN
COUNTY OF MUSKEGON
REGISTER OF DEEDS

1995 DEC 13 PM 4:10

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Muskegon
(County)

Located In: Corner Code #

- | | | | | | |
|---------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey | T | 11N | R | 16W | D-9 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous
Property in Sec. | S | T | R | | |
| | S | T | R | | |

**SURVEY &
REMONUMENTATION**

Register of Deeds Stamp & File Number

APR 04 1996

4. Lot No. _____, Recorded Plat COMMISSION
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Stephen V. Vallier, P.S., in a field survey on May 1, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO set corner S 57 deg. E 37 Links 6" White Oak
 N 73 deg. W 26 Links 6" White Oak

1958 M. Buck Found Iron survey number 45-58
 1960 MSHD N 50 deg. E 41.15' 14" Locust
 Found 1/2" Iron S 40 deg. W 36.88' 36" Black Oak
 NW 44.94' Telephone Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" Iron beside 1" Iron Pipe - also found 1" Iron Pipe located 4' South and 3' East of "T" iron.
 N 45 deg. E 24" Stump

Accepted position of corner due to historical usage and documentation.

POSITION OF SAID
 RECORDED CORNER
 REVIEWED & RATIFIED
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

aug 7, 1995 SW

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" x 30" Cast Iron Monument with County Survey Cap in place of "T" iron

- S 28 deg. E 58.68' Power Pole (found nail with MDOT tag SW side)
- S 42 deg. W 43.83' MI Concrete Box (NE corner)
- S 39 deg. W 102.12' 24" Oak (found spike in NW side)
- N 37 deg. W 88.26' Power Pole (found PK nail SW side)
- N 41 deg. E 42.50' Telephone Pole (found nail with MDOT tag NW side)
- N 57 deg. E 46.08' Utility Pole (set PK nail SE side)

Recorded by Steph V. Vallier Date 12/12/95
 Surveyor's Michigan License No. 28428