

**SURVEY &
REMONUMENTATION**

LIBER **1810** PAGE **622**

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

APR 28 1995

1994 DEC 29 AM 10:18

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Carris Carter
REGISTER OF DEEDS

For corners in

<u>Muskegon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>16W</u>	<u>E 3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A 164b

Register of Deeds Stamp & File Number

I, Ralph W. VanRiper, in a field survey on June 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to sections 4, 5, 8, and 9,
T 11 N, R 16 W, Dalton Township

Set post June 25, 1837, by GLO Surveyors

Spruce 12" S 41° W 90 L
B Oak 12" N 49° E 1.42 C

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe, recorded by Donald L. Bissell, RLS #18655,
Liber 1377, Page 433, January 28, 1987.

N 62° E 64.87' 6" Jack Pine
N 80° E 90.50' 30" oak
S 59° E 36.98' Power Pole
S 53° W 45.55' Sign Post

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

May 2, 1994 su

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" by 20" Cast Iron Monument with
County Surveyor Cap in Monument Box.

N 60° E 64.81' Fd. Surveyors Tag NW side 6" Pine
S 37° E 51.48' Set nail SW side 6" Pine
S 35° W 78.24' Fd. nail SE side 8" Pine
N 70° E 90.50' Fd. nail South side 30" Oak
S 60° E 37.05' Fd. nail North side Power Pole
S 60° W 75.30' Set nail SE side 6" Oak



Signed by *Ralph W. VanRiper*
Surveyor's Michigan License No. 16946

Date 12/27/94