

**SURVEY & REMONUMENTATION**

APR 04 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*L 1871 Pg 602*

*A1726*

For corners in  
**Muskegon**  
(County)

Located In: Corner Code #

1. Public Land Survey	T	<u>11N</u>	R	<u>16W</u>	E-12
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

STATE OF MICHIGAN  
 COUNTY OF MUSKEGON  
 REGISTER OF DEEDS  
 1995 DEC 18 PM 4:14  
*Charles W. ...*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	13	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Stephen V. Vallier, P.S., in a field survey on November 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO set corner

1950's MCRC - Oak stake

W	11.50'	18" Black Oak
SE	46.10'	18" Twin Oak
E	2624.00'	Center Section

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" x 30" Cast Iron Monument with County Survey Cap. Check LCRC Liber 1337 Page 641 witness.

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

*Nov. 13, 1995*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Found 4" x 30" Cast Iron Monument with County Survey Cap.

N 30 deg. E	90.60'	Power Pole (nail)
S 38 deg. E	4.10'	6" Pine (nail)
S 05 deg. W	24.70'	6" Maple (nail)
S 80 deg. W	11.93'	6" Oak (nail)
S 81 deg. E	7.05'	4" Oak (nail)
N 30 deg. E	5.55'	4" Pine (nail)



Signed by *Stephen V. Vallier* Date *Nov. 13, 1995*

Surveyor's Michigan License No. 28428