

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1995 DEC 28 AM 8:45

For corners in
Muskegon
(County)

Located In: Corner Code #

- 1. Public Land Survey T 11N R 16W F 6
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
 - 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R NOV 28 2000
 - 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- SECTION**
- 4. Lot No. _____, Recorded Plat _____
 - 5. Private Claims _____

I, Mark F. Fairchild, Register of Deeds, Muskegon County, Michigan, do hereby certify this to be a true copy of the instrument recorded in my office, reception record appearing thereon.

Mark F. Fairchild

A01760

Register of Deeds Stamp & File Number

I, Ralph W VanRiper, in a field survey on May 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
6												
6	16	17	15	14	13							
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Center of Section 16, T 11 N, R 16 W
Not set by GLO Surveyors

MCRC (1950's) Nothing shown at corner
MCRC Witnesses Book, 3 Witnesses to corner set in July of 1966 at intersection of 1/4 lines by Charles F. Lewandowski, RLS No. 7867

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Concrete Monument at corner, Verified location by existing witnesses.

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990



SW 5/2/95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Aluminum County Survey cap on top of existing Concrete Monument.

- N 10° E 3.53' Set Spike in W side of 4" Birch
- S 45° E 12.67' Set Spike in E side of 6" Maple
- S 15° W 12.00' Set Spike in NW side of 8" Elm
- S 35° W 27.05' Found Spike in SE side of 12" Maple
- N 60° W 34.68' Found Spike in SW side of 12" Birch
- N 10° W 29.66' Found Spike in E side of 10" Maple

I, Mark F. Fairchild, Register of Deeds, Muskegon County, Michigan, do hereby certify this to be a true copy of the instrument recorded in my office, reception record appearing thereon.

Mark F. Fairchild

Signed by Ralph W. Van Riper
Surveyor's Michigan License No. 16946

Date Dec. 19, 1995