

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LIBER 1810 PAGE 627

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1994 DEC 29 AM 10:18

Carrie Carter
REGISTER OF DEEDS

For corners in

<u>Muskegon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>16W</u>	<u>G 4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A1651

Register of Deeds Stamp & File Number

I, Ralph W. VanRiper, in a field survey on December 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner between Sections 9 & 10, T 11 N, R 16 W, Dalton Township

Set post June 23, 1837, by GLO Surveyors

16" Pine S 24° E 35 L
7" W Oak N 17° E 55 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" steel bar as per Muskegon County Road Commission Witness book, recorded by Duane F. Wood, RLS #24625, Liber 1156, Page 375, November 27, 1978.

N 10° W Triple Oak 6.10'
N 60° E 12" Oak 19.50'
S 30° W 12" Oak 10.10'

POSITION OF SAID
RECORDED CORNER
REVIEWED & ENDORSED
BY MUSKEGON COUNTY
PEER GROUP IN CONFORMANCE
WITH P.A. 275, OF 1980

May 2, 1994 SW

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" by 20" Cast Iron Monument with County Surveyor Cap.

N 10° E 6.06' Fd. nail West side triple oak.
N 30° E 41.24' Fd. nail East side 24" oak.
East 19.53' Fd. nail South side 14" oak.
S 25° E 47.78' Set nail East side power pole.
South 30.12' Set nail West side 14" oak.
S 85° W 49.30' Fd. nail South side 18" oak.



Signed by *Ralph W. VanRiper*
Surveyor's Michigan License No. 16946

Date 12/27/94