

**SURVEY &  
REMONUMENTATION**

LIBER **1810** PAGE **628**

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD

APR 28 1995

1994 DEC 29 AM 10:18

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Carris Carter*  
REGISTER OF DEEDS

For corners in

<u>Muskegon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>16W</u>	<u>G 5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*A1652*

Register of Deeds Stamp & File Number

I, Ralph W. VanRiper, in a field survey on November 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Section corner between sections 9, 10, 15, & 16,  
T 11 N, R 16 W, Dalton Township

Set post June 23, 1837, by GLO Surveyors

16" White Oak S 44° E 24 L  
18" White Oak N 11° E 36 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe as per Muskegon County Road Commission  
Witness book, recorded by Duane F. Woods, RLS #24625,  
Liber 1156, Page 375, November 27, 1978.

N 15° W 18" Oak 10.55'  
S 60° W 18" Oak 29.50'  
S 45° E 18" Oak 19.65'

POSITION OF SAID  
RECORDED CORNER  
REVIEWED & APPROVED  
BY MUSKEGON COUNTY  
DEED GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1930

*May 2, 1994 SW*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" Cast Iron Monument with County Surveyor Cap.

N 10° E 10.66' Fd. nail West side 24" oak.  
S 44° E 19.76' Fd. nail Southwest side 20" oak.  
S 68° W 29.45' Set nail North side 24" stump.  
N 48° W 57.19' Set PK nail Northeast side power pole.  
S 26° W 20.06' Set nail East side 10" oak.  
N 88° W 79.06' Set nail South side 10" oak.



Signed by *Ralph W. Van Riper* Date 12/27/94  
Surveyor's Michigan License No. 16946