

**SURVEY &
REMONUMENTATION**

APR 28 1995

LIBER 1810 PAGE 629

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1994 DEC 29 AM 10:18

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Carrie Carter
REGISTER OF DEEDS

For corners in

Muskegon (County)	Located In:	Corner Code #
1. Public Land Survey	T 11N R 16W	G 6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

A1653

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ralph W. VanRiper, in a field survey on November 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1/4 corner between Sections 15 and 16, T 11 N, R 16 W, Dalton Township

Set post June 23, 1837, by GLO Surveyors

- 9" Birch S 55° W 19 L
- 7" Birch N 55° E 15 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe as per Muskegon County Road Commission Witness book.

- WNW 45.12' Fence post
- NW 40.86' 10" poplar
- SW 43.20' 6" willow

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990
May 2, 1994 suv

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" by 30" Cast Iron Monument with County Surveyor Cap.

- N 80° W 41.55' Fd. nail South side 12" poplar.
- N 38° W 63.08' Fd. nail South side 12" poplar.
- S 50° W 58.25' Set nail Southeast side 6" poplar.
- N 39° E 41.15' Set nail Southeast side 12" poplar.
- S 69° E 24.90' Set nail South side 8" poplar.
- S 29° E 44.60' Set nail North side 8" poplar.



Signed by *Ralph W. Van Riper*
Surveyor's Michigan License No. 16946

Date 12/27/94