

**SURVEY &
REMONUMENTATION**

APR 28 1995

LIBER 1810 PAGE 634

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1994 DEC 29 AM 10:19

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Carrie Carter
REGISTER OF DEEDS

For corners in

Muskegon
(County)

Located In:

Corner Code #/

- | | | |
|---------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>11</u> N R <u>16</u> W | H 6 |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling
in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous
Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

A1658

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ralph W. VanRiper, in a field survey on November 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Center of Section 15, T 11 N, R 16 W, Dalton Township.
Not set by GLO Surveyors

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod as per Muskegon County Road Commission
Witness book.

- SW 38.20' 10" Pine
- N 59.80' Iron
- E 49.70' 20" Pine
- NNW 41.38' Twin 14" Oak
- WNW 26.77' 32" Oak

POSITION OF SMD
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

May 2, 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" by 20" Cast Iron Monument with
County Surveyor Cap.

- S 88° E 49.70' Set nail South side 24" Pine,
- N 19° W 41.38' Set nail West side Twin 14" Oak,
- S 30° E 19.15' Set nail Southwest side 10" Sassafras
- S 26° W 44.36' Set nail East side 10" Maple
- N 70° W 26.72' Set nail South side 30" Oak
- N 14° E 20.31' Set nail West side 10" Oak



Signed by *Ralph W. Van Riper*

Date 12/27/94

Surveyor's Michigan License No. 16946