

**SURVEY &
REMONUMENTATION**

LIBER **1810** PAGE **643**

APR 28 1995

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

1994 DEC 29 AM 10:19

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Carrie Carter
REGISTER OF DEEDS

For corners in

<u>Muskegon</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>11N</u> R <u>16W</u>	<u>J 5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A1667

Register of Deeds Stamp & File Number

I, Ralph W. VanRiper, in a field survey on November 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1/4 Corner between Sections 11 and 14, T 11 N, R 16 W, Dalton Township.

Set post June 12, 1837, by GLO Surveyors

8" Beech S 20° W 4 L
10" W Oak N 20° E 5 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe as per Muskegon County Road Commission Witness book, recorded by John I. Nelson, LLS #21273, Liber 1149, Page 718, September 20, 1978.

AZ. 36° 42.13' Spike in SE side 12" B. Oak
AZ. 134° 50.15' Fd. spike in SW side of 14" Maple
AZ. 182° 49.61' Set nail with tag in E side of Power Pole
AZ. 359° 39.10' Fd. spike in E side of 10" W. Oak

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

May 2, 1994 sw

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Surveyor Cap.

S 02° W 49.61' Fd. spike in E side of Power Pole
S 46° E 50.20' Fd. spike in SW side of 14" Maple
N 36° E 42.13' Fd. spike in SE side of 14" Oak
N 01° W 39.10' Fd. spike in E side of 10" Oak
N 45° W 44.91' Set spike in N side of Telephone Pole
S 60° E 69.30' Set spike in S side of 12" Oak



Signed by *Ralph W. Van Riper*
Surveyor's Michigan License No. 16946

Date 12/27/94