

**SURVEY &
REMONUMENTATION**

LIBER 1810 PAGE 645

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 29 AM 10:20

COMMISSION

Carrie Carter
REGISTER OF DEEDS

For corners in

Muskegon
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>11N</u> R <u>16W</u> | <u>K 2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

A1669

Register of Deeds Stamp & File Number

I, Ralph W. VanRiper, in a field survey on May 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1/4 Corner between Section 1 and 2, T 11 N, R 16 W
Dalton Township

Not set by GLO Surveyors

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rod as per Muskegon County Road Commission Witness book. Recorded by Donald W. Schiele, RLS #23517 February 6, 1980, Liber 1180, Page 677, 1" pinched iron pipe.

- 14" Oak SE 38.00'
- 14" Stump S 59.61'
- SE Hse. Cor SSW 25.81'
- 8" Locust NNE 23.75'

Recorded by Stanley Shackelford, RLS #30100, May 9, 1990, Liber 1518, Page 01, Fd. iron rod

- SSW 25.81' Hse. #6597
- NNE 23.75' 8" Locust
- SE 37.98' 14" Oak

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Surveyor Cap.

- S 83° E 46.42' NW corner block foundation
- N 18° E 23.75' Fd. nail E side 16" Locust
- S 3° W 59.65' Fd. nail E side 12" stump
- N 43° W 36.69' Fd. nail S side 28" stump
- S 55° W 65.04' Set nail W side 10" Willow
- North 32.90' Fd. 1/2" pipe

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990
Feb 11, 1994 su



Signed by *Ralph W. Van Riper*

Date 12/27/94

Surveyor's Michigan License No. 16946